



ಭಾರತೀಯ ಮಾಹಿತಿ ತಂತ್ರಜ್ಞಾನ ಸಂಸ್ಥೆ ಧಾರವಾಡ  
भारतीय सूचना प्रौद्योगिकी संस्थान धारवाड़

**INDIAN INSTITUTE OF INFORMATION TECHNOLOGY DHARWAD**

[Institute of National Importance by an Act of Parliament]

Ittagatti Road, Near Sattur Colony, Dharwad 580009, Karnataka, India.

Website: [www.iiitdwd.ac.in](http://www.iiitdwd.ac.in)

**NOTICE INVITING QUOTATION (NIQ)**

NIQ No.: IIITDWD/Estate/2025-26/755

Date of Issue: 01.04.2026.

Last Date & Time of Submission: 08.04.2026 up to 05:00 Pm

Quotations will be opened on the next day and the qualified bidder will be communicated accordingly.

Place of Submission: Engineering section, 2nd Floor - Pie - Building, IIIT Dharwad Campus, Dharwad - Karnataka

Name of Work: "Laying of HDPE pipeline for water supply".

Estimated cost: ₹3,11,206.00/-

Work completion period: 25 days

The bidders are required to quote rates strictly as per the Schedule of Quantities (BOQ). The quotation will not be accepted in any format other than the prescribed format. The completed set in a sealed envelope shall be addressed to:

Engineering section, 2nd Floor - Pie - Building , IIIT Dharwad Campus, Dharwad - Karnataka

The quotations will be received up to 05:00 PM on 08.04.2026 along with all necessary documents in the Engineering Section, Pie-Building, IIIT Dharwad. Quotations will be opened on the next day and the qualified bidder will be communicated accordingly.

For any clarifications & Queries related to the BoQ.  
Contact Email ID: [aee@iiitdwd.ac.in](mailto:aee@iiitdwd.ac.in) (AEE, IIIT Dharwad)



Registrar  
IIIT Dharwad

ಕುಲಸಚಿವರು/ ಕುಲ ಸಚಿವ/ REGISTRAR

IIIT DHARWAD

Near Sattur Colony, Ittagatti Road,

Dharwad - 580 009

Page No: 01



ಭಾರತೀಯಮಾಹಿತಿತಂತ್ರಜ್ಞಾನಸಂಸ್ಥೆ ಧಾರವಾಡ  
भारतीयसूचनाप्रौद्योगिकीसंस्थान धारवाड़

**INDIAN INSTITUTE OF INFORMATION TECHNOLOGY DHARWAD**

[Institute of National Importance by an Act of Parliament]

Ittagatti Road, Near Sattur Colony, Dharwad 580009, Karnataka, India.

Website: [www.iiitdwd.ac.in](http://www.iiitdwd.ac.in)

Sealed envelope quotations shall be superscripted with: "Name of Work, RFQ No., and Contact details"

The agency has to submit the following self-attested copies of documents along with the annexure (enclosed):

1. GST Registration Certificate.
2. **Annexure-1,**
3. **Annexure-2**

**NOTE: Any quotes received after 05:00 PM hours on 08/04/2026 will not be accepted. Name of the Work / Ref number and Firm name along with mobile no should be mandatorily written on the sealed cover.**

Seal and signature of bidder with date.

Page No: 02



ಭಾರತೀಯಮಾಹಿತಿತಂತ್ರಜ್ಞಾನಸಂಸ್ಥೆಧಾರವಾಡ  
 भारतीयसूचनाप्रौद्योगिकीसंस्थानधारवाड़

**INDIAN INSTITUTE OF INFORMATION TECHNOLOGY DHARWAD**

[Institute of National Importance by an Act of Parliament]

Ittagatti Road, Near Sattur Colony, Dharwad 580009, Karnataka, India.

Website: [www.iiitdwd.ac.in](http://www.iiitdwd.ac.in)

### TERMS AND CONDITIONS

1. The work shall be carried out as per latest CPWD/KPWD specifications for Civil works with up-to-date correction slips and as per direction of Engineer-in-Charge.
2. Rates quoted shall remain firm till completion of entire work and shall not attract any escalation under any circumstances. Quantities mentioned in BOQ may increase or decrease as per requirement of the Institute.
3. IIIT Dharwad shall not be held responsible for delay in submission of quotation.
4. **Bidders are advised to inspect and examine the area before submitting quotations and obtain all necessary information regarding risks and contingencies. No extra charges shall be allowed on account of misunderstanding.**
5. Work will be executed as per latest KPWD/CPWD Works Manual & CPWD General Conditions of Contract for Maintenance Works.
6. **Rates quoted shall be inclusive of all applicable taxes Statutory deductions like labourcess, TDS etc. shall be deducted from the bill as per prevailing rules.**
7. The contractor shall monitor the quantum of work vis-à-vis balance items and obtain approval before executing extra/deviation items.
8. Payment will be released based on actual measurements and satisfactory completion certified by Engineer-in-Charge. No advance payment shall be made to the contractor.
9. The contractor shall clean the site thoroughly of debris/materials, satisfaction of Engineer-in-Charge.
10. Delay Penalty: 0.5% of total work order value per week of delay subject to maximum 10% of accepted value of work.
11. For substandard/incomplete work penalty may be imposed and suitable recovery will be made from contractor's bill.
12. Materials (PVC pipes, etc.) shall be of approved make/quality and shown to get approved from Engineer-in-Charge before execution.
13. The contractor shall ensure safety of working personnel and comply with all statutory safety norms.
14. Competent Authority of IIIT Dharwad reserves the right to accept or reject any or all quotations without assigning reason.
15. Financial loss due to negligence/default shall constitute sufficient ground for annulment of award and blacklisting/debarment for two years.
16. Use of correction fluid in quotation is not permitted and such quotations are liable for rejection.
17. Quotation shall remain valid for 75 days from the date of opening.
18. Any dispute shall be subject to territorial jurisdiction of Dharwad Courts, Karnataka only.



ಭಾರತೀಯಮಾಹಿತಿತಂತ್ರಜ್ಞಾನಸಂಸ್ಥೆಧಾರವಾಡ  
 भारतीयसूचनाप्रौद्योगिकीसंस्थानधारवाड़

**INDIAN INSTITUTE OF INFORMATION TECHNOLOGY DHARWAD**

[Institute of National Importance by an Act of Parliament]

Ittagatti Road, Near Sattur Colony, Dharwad 580009, Karnataka, India.

Website: [www.iiitdwd.ac.in](http://www.iiitdwd.ac.in)

**Annexure -1**

**PARTICULARS TO BE FILLED BY THE BIDDER**

Name of the Bidder: \_\_\_\_\_

GST No.: \_\_\_\_\_

PAN No.: \_\_\_\_\_

Complete Address: \_\_\_\_\_

Contact Person Name & Mobile No.: \_\_\_\_\_

Email ID: \_\_\_\_\_


Bank Details of the agency: \_\_\_\_\_

Experience Details (Attach Certificates mentioning with page number):

\_\_\_\_\_

**Seal and signature of bidder with date.**

**Page No: 04**



**Annexure-2**

**SCHEDULE OF QUANTITIES (BoQ)**

**24 X 7 WATER SUPPLY HDP PIPELINE LAYING WORK**

SINO	PARTICULAR	UNIT	LENGTH	BREADTH	DEPTH	RATE	QTY	AMOUNT
1	Earth work excavation for pipeline trenches in all kinds of soils by mechanical means as per drawing and technical specifications including setting out, construction of shoring strutting, barricading, caution lights, bracing, using sight rails & bonding roads at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required, utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. All kinds of soils. Depth upto 1.50m - soil @70%	m <sup>3</sup>	210	0.70	1.10		161.7	
2	Providing, laying and jointing HDPE pipes of specified grade and confirming to IS 4984-2016 with latest amendments and conveying to work site including loading and unloading at both destinations and rolling and lowering in to trenches, laying true to line and jointing of pipes and specials with electrofusion welding, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe allround to a depth of not less than 15cms. with soft gravel or selected earth available from the excavation,	m	210				210	

Seal and signature of the bidder with date.





5	shall be deducted from the SR rates of valves and provision for corresponding dia MS flanges should be made in the estimate.) etc. complete Providing and fixing of HDPE water meter box with locking arrangement to protect the water meter of class 'B' Multijet type of size 15 to 32 mm including HDPE box with base dia 300mm X lid dia 200mm X height 250mm with openable lid and the cover is buried below GL with lid flush with GL including earth work excavation for 600mm X 600mm and base sand filling for 100 mm thick over which the cover is placed and enclosed by pCC 1:2:4 using 12-20mm BG jelly for an height of 150mm and refilling with excavated earth for balance 100mm height, disposal of excess earth with all lead and lifts with appurtenances complete as per drawing enclosed etc., complete	Each	1					1		
6	Providing and executing the joining of HDP pipeline with DI pipeline at the source location and joining of HDP pipeline with CPVC pipeline at the WTP delivery point, including supplying and fixing of all required couplers, welding, jointing materials, and necessary fittings. The rate shall be inclusive of all fixtures, accessories, labor, tools, and all other incidental charges required to complete the work in all respects.	Joints						2		
7	Miscellaneous									
									Total	
									GST 18%	
									Grand Total	